BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17820

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/01/2015-16, Date:01.09.2015

Improvements to Roads and Drains at MS Palya & Surrounding Roads in Ward No. 11 Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K S CHOWDAREDDY		
				In Figures		In Words
1	507.15	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	75.0	38036.25	Rupees Seventy Five Only
2	491.78	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4730.0	2326119.40	Rupees Four Thousand Seven Hundred Thirty Only
3	328.1	size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of	Cum	5500.0	1804550.00	Rupees Five Thousand Five Hundred Only
4	2681	and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc complete as per	Sqm	90.0	241290.00	Rupees Ninety Only
5	269	depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand	Rmt	130.0	34970.00	Rupees One Hundred Thirty Only
6	13.5	of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @	Cum	5800.0	78300.00	Rupees Five Thousand Eight Hundred Only
7	0.81	straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks	Tonne	78000.0	63180.00	Rupees Seventy Eight Thousand Only
8	105	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	300.0	31500.00	Rupees Three Hundred Only
9	507.15	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. etc complete as per specifications and directions of engineer in charge of the work	Cum	69.49	35241.85	Rupees Sixty Nine and Forty Nine Paise Only
		Total			**4653187.50**	

K. S. Chowdareddy

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

1/3/16